

Property Arts Inc.
3220 West Lansing
Broken Arrow, Oklahoma 74012
(918) 893-5560 Fax: (918) 893-5562

May 11, 2016

ADDENDUM #2

Re: Oak Grove Fire District Project

A1519

1. Refer drawings sheet S-1 Site Plan septic system: A percolation test has not been performed and the extents of the leach field are undetermined. Bidders are to include an allowance of \$4,000 for the installation of the leach field. Actual cost of install of leach field to be adjusted at completion by way of Add/Deduct Change Order.
2. Refer drawings sheet E-1 Electrical Plan: Add the following notes:
 - a. All 220volt receptacles in Apparatus Bay are to be 50 amps. General Contractor to verify amperes with Owner prior to install.
 - b. All Over Head Door motors are to be single phase.
3. Refer drawings sheet E-1 Electrical Plan Light Fixture Schedule: Change low bay light fixture "Big Ass Light HBL1-10K" to "Lithonia IBZ432L WGX - (4) 32W T8 120V.

Thank you,
Property Arts Inc.


Darrell R. Byrd, AIA
Architect

