

Lori Hendricks
Wagoner County Clerk



307 E. Cherokee St.
Wagoner, OK
74467
918.485.7716
Fax 918.485.7718

ADDENDUM 1 60' SPAN STEEL BRIDGE INSTRUCTIONS TO BIDDERS

The contractor will provide the County with turnkey construction of a 60' span steel bridge using surplus Crosstown Beams. Construction activities for this project include the following:

1. The County will provide for the preparation of the Crosstown Beams, including the hauling of the beams from the County yard to the jobsite. The Contractor will be required to off load and handle the beams at the construction site.
2. Pile driving procedures adequate to achieve minimum pile bearing
3. Structural steel welding to fabricate the superstructure in-place including guardrail installation.
4. Install the stay-in-place formwork and cast the reinforced concrete deck. The County will supply the concrete for this project. The contractor will provide the concrete pump truck, if necessary.
5. The County will perform the demolition, provide the fill material(s), and perform the approach backfill earthwork.

WAGONER COUNTY 60' BRIDGE PLANS

Sheet 3 – ABUTMENT DETAILS: Summary of Quantities

- Bidder shall bid three (3) rows of horizontal bracing.
- Bidder shall bid 10 gauge Sheet Piling at 70 pieces totaling 1540 LF.
- Guard Rail – Contractor is to provide quantity of Guard Rail for the bridge structure only, including end sections on all four corners. Quantity = 120 LF. Transition pieces and Anchor assembly bolts will be provided by the contractor to be installed by the County.

If you have further questions regarding the content of the construction bid, please feel free to contact Monty Proctor at 918-906-3825.